

# CITY OF SANTA MARIA CELL 1 EXTENSION LINER DESIGN AND CONSTRUCTION PROJECT



PRESENTED BY  
*THE CITY OF SANTA MARIA*  
*HERB CANTU*  
*SOLID WASTE MANAGER*

*SWT ENGINEERING*  
*JEREMY BOTICA, P.E., M.S.*  
*PROJECT MANAGER*

April 6, 2022



**Santa  
Maria**



# CITY OF SANTA MARIA CELL 1 EXTENSION LINER DESIGN AND CONSTRUCTION PROJECT

*HERB CANTU  
CITY OF SANTA MARIA  
SOLID WASTE MANAGER*

- ❖ 13 Years In Solid Waste Industry
- ❖ 13 Years As Solid Waste Manager
- ❖ SF Giants Supporter

*JEREMY BOTICA, P.E., M.S.  
SWT ENGINEERING  
PROJECT MANAGER*

- ❖ 14 Years In Solid Waste Industry
- ❖ 8 Years As Project Manager
- ❖ LA Dodgers Supporter



**Santa  
Maria**



**ENGINEERING**



[www.swteng.com](http://www.swteng.com)

# CELL 1 EXTENSION LINER PRESENTATION OUTLINE


- ❖ Site Background
- ❖ Site Overview / Goals
- ❖ NHIS Over Liner / Settlement
- ❖ Phasing Management
- ❖ Existing/Proposed LFG Network
- ❖ Liner Design and Join
- ❖ Leachate Collection
- ❖ Solar Power
- ❖ Questions



The **Santa Maria Regional Landfill** is located 260 miles South of San Francisco and 160 miles north of Los Angeles, in the city of Santa Maria which is in Santa Barbara County




## SITE LOCATION



LOCATION MAP

SCALE: 1"=2 MI



VICINITY MAP

SCALE: 1"=6 MI



# Santa Maria



ENGINEERING



# LANDFILL OVERVIEW



- ❖ The SMRL has been operating since the 1950s and is owned and operated by the City of Santa Maria.
- ❖ The facility acreage consists of a total of approximately 290 acres.
- ❖ The current permitted disposal area footprint is approximately 247 acres.
- ❖ Disposal operations are currently being conducted in the Active Area (lined Cell 1 area).



Santa  
Maria

**SWT**  
Civil & Environmental

**ENGINEERING**



www.swteng.com

# LANDFILL OVERVIEW



## Solid Waste Collections

- ❖ Perform residential and commercial refuse, recycling, and green waste collections for the City of Santa Maria
- ❖ Customer Accounts
- ❖ Residential – over 19,000
- ❖ Commercial – over 1,500
- ❖ Comprised of 27 employees
- ❖ Residential collection operates Monday through Friday
- ❖ Hours of Operation 6:00 a.m. – 2:30 p.m.
- ❖ Commercial collections operates Monday through Saturday
- ❖ Hours of Operation 3:30 a.m. – 12:00 p.m.



# LANDFILL OVERVIEW

## 2020 Figures\*

- ❖ Open 7 days a week (7:00 a.m. – 4:00 p.m.)
- ❖ Closed 7 holidays a year
- ❖ Buried 146,760 tons of MSW
- ❖ Over 60,000 tons from our Collections Fleet
- ❖ Average 409 tons/day (818,000 lbs./day)
- ❖ City-wide diverted over 90,000 tons for recycling and composting
- ❖ Busiest Day: 1081 tons MSW & recycling
- ❖ 114,479 vehicles cross the scales
- ❖ Average 319 vehicles/day (1 every 1:40)
- ❖ Busiest day: 504 vehicles
- ❖ \*Note: Does not include NHIS tons



Santa  
Maria



ENGINEERING




# PROJECT GOALS

- ❖ Extend the site life/Provide additional time to open the new facility
- ❖ Convert NHIS capacity to Class III refuse disposal capacity
- ❖ Expand the Subtitle D liner area
- ❖ Provide a robust design to facilitate regulatory agencies permitting
- ❖ Maintain the existing solid waste facility permit



# SITE PLAN




Santa  
Maria



ENGINEERING




# LANDFILL CAPACITY AS OF JAN 1, 2021



	Airspace (CY)	Current Yearly Refuse Fill Rate (CY)	Remaining Years
NHIS - Current	842,230	72,500	11.6
CELL 1 - Current	706,670	202,270	3.5
CELL 2 - Current	352,000	202,270	1.75



# LANDFILL CAPACITY AS OF JAN 1, 2022



	Airspace (CY)	Current Yearly Refuse Fill Rate (CY)	Remaining Years	Extension Airspace (CY)	Remaining Years
NHIS - Current	842,230	72,500	11.6	476,785	6.6
CELL 1 - Current	706,670	202,270	3.5	1,535,000	7.5
CELL 2 - Current	352,000	202,270	1.75	0	0






- ❖ Reallocated 352,000 CY from CELL 2
- ❖ Repurposed 350,000 CY of NHIS Airspace To Class III Waste




# SITE SETTLEMENT

Evaluated actual settlement within the Closed Active Area at two different locations between the topographic aerial surveys of October 2008 and October 2018.



❖ Area 2 maximum settlement of approximately 2.8 feet.

❖ Area 1 maximum settlement of approximately 1.5 feet.



- ❖ 6% Grade
- ❖ 36 ft of fall from North to South
- ❖ All Gravity Leachate Convenience System



# Santa Maria



**ENGINEERING**






Santa  
Maria

- ❖ 6% Grade
- ❖ 36 ft of fall from North to South
- ❖ All Gravity Leachate Convenience System




# PHASING MANAGEMENT



❖ NHIS Subgrade Grading 110,000 CY



# PHASING MANAGEMENT



Santa Maria

❖ Unclassified Fill 35,000 CY






ENGINEERING



www.swteng.com

# PHASING MANAGEMENT



- NOTES:
1. SEE SHEET 2 FOR LEGEND.
  2. CONTRACTOR TO ENSURE 24" MINIMUM COVER OVER LINER AT ALL TIMES WHEN INSTALLING BERM GAP FILLS WITH CONSTRUCTION EQUIPMENT.
  3. SEE SHEET 6 FOR ALL LANDFILL GAS IMPROVEMENTS.
  4. EXCAVATION AT THE LINER JOIN AREA MAY ENCOUNTER REFUSE WHICH SHALL BE TAKEN TO THE ACTIVE DISPOSAL AREA. ANY CLEAN SOIL CAN BE USED AS FOUNDATION MATERIAL.

DATE OF TOPOGRAPHY: DECEMBER 31, 2019 MARK CHANGES NO CHANGES RESIDENT ENGINEER DATE FIELD CHANGES	PREPARED BY: <b>SWT</b> Civil & Environmental Engineering 800-C SOUTH ROCHESTER AVENUE OAKLAND, CALIFORNIA 94612	CITY OF SANTA MARIA DESIGNED BY: [Signature] DRAWN BY: [Signature] CHECKED BY: [Signature]	SANTA MARIA REGIONAL LANDFILL CELL 1 EXTENSION LINER CONSTRUCTION PROJECT BERM GAP FILL AND LINER PLAN
	PREPARED UNDER THE SUPERVISION OF: [Signature] CIVIL ENGINEER	SUBMITTED BY: JERRY A. BODIA P.E., M.S., 471471 PROJECT MANAGER	DATE: 04-21-2019 FILE NO.: 2125.08 SCALE: AS SHOWN SHEET NO.: 8 TOTAL SHEETS: 19



Santa Maria

❖ Gap Berm Placement 37,000 CY



ENGINEERING



# GAP BERM SEQUENCING




Santa  
Maria



ENGINEERING







www.swteng.com



- ❖ 9 wells under liner construction
- ❖ 4 other well adjustments
- ❖ 2 geocomposite wells





# EXISTING LANDFILL GAS NETWORK



❖ Extended remote wellheads from under the liner system

# LANDFILL GAS GEOCOMPOSITE COLLECTION



**Santa  
Maria**


- ❖ Blanket gas collection layer under the floor liner system
- ❖ Geocomposite perimeter gas collection



**ENGINEERING**




# LINER DESIGN



**NOTES:**

1. THE UPPER 6-INCHES OF NHIS MATERIAL WILL BE SCARIFIED AND RE-COMPACTED PRIOR TO LINER PLACEMENT.
2. VENEER FILL TO BE PLACED WHERE SPECIFIED DURING SITE INSPECTION.

**BASE LINER**  
NTS



**NOTES:**

1. HDPE GEOMEMBRANE TO BE COLORED WHITE (WHITE SIDE UP).
2. VENEER FILL TO BE PLACED WHERE SPECIFIED.
3. THE UPPER 6-INCHES OF NHIS MATERIAL WILL BE SCARIFIED AND RE-COMPACTED PRIOR TO LINER PLACEMENT.

**SLOPE LINER**  
NTS



Santa  
Maria



**ENGINEERING**




# LINER CONSTRUCTION



Santa  
Maria



# GRAVITY LEACHATE CONVEYANCE SYSTEM





Santa  
Maria



ENGINEERING



# CELL 1 SUMP RISER TIE-IN



**Santa  
Maria**

- ❖ Outfall piping required refuse excavation.
- ❖ Installed riser cleanout outlets

**SWT**  
Civil & Environmental  
**ENGINEERING**




# LINER JOIN



- ❖ Liner tie in was designed to not have more than 1 foot of potential leachate head on the liner.
- ❖ Geocomposite collection went to existing Cell 1 tie in.

- ❖ As-Builts didn't match up to design.
- ❖ Required additional refuse excavation.
- ❖ Slightly steeper slopes to join.



# SOLAR POWER PUMP SUPPLY



- ❖ Removed existing 480V power to contact water tank/pump.
- ❖ Installed solar to run new pump system.



Santa  
Maria

# CONSTRUCTION TIME LAPSE



Santa  
Maria





# QUESTIONS



Santa  
Maria

